

Independent Engineer's Report: Cottonwood Solar I

Report date: July 31, 2026

Prepared for: prospective tax credit purchasers and lenders

1. Project Description

The Project is a 100 MWac / 135 MWdc single-axis tracking solar photovoltaic facility in Montgomery County, Illinois, owned by Cottonwood Solar I, LLC, with 27 central inverters and a 34.5/138 kV project substation. The design is consistent with the interconnection agreement.

2. Construction History

The EPC contractor received full notice to proceed on December 18, 2025. Mobilization occurred in early January 2026. On-site physical work of a significant nature, beginning with pile installation for the tracker foundations, commenced on January 12, 2026.

The sponsor has advised that it also relies on off-site physical work on the custom main power transformer, performed under a binding written contract, as the start of construction. We have not reviewed the manufacturer's records and express no opinion on the tax treatment of off-site work.

3. Schedule

As of the report date, the EPC schedule forecasts substantial completion on November 15, 2026 and placed-in-service on or about November 30, 2026, contingent on main power transformer delivery in September 2026.